

**PROPOSED DRAFT
February 2015**

551.03.8 Testing and Acceptance of Concrete

C. Acceptance of Concrete.

1. Classes General, Deck, Pave, Structure, Overlay and Drilled Shaft Concrete.

The overall lot pay factor (OLPF) will be calculated for bid items as shown in Table 551-10 and will be applied as a line item adjustment on the estimate.

TABLE 551-10

Class	Items
Deck	Include all items except metal bridge rail and bridge deck repair
Drilled Shaft	Include all items
Overlay-Sf	Include all items
Pave	Include all items
Structure	Include concrete class bid items
General	Include concrete class bid items Include items in Subsection 608 Include items in Subsection 609 Include items measured by the volume Exclude all other items

Note 1: The OLPF may be evaluated on other contract items that have significant equivalent concrete quantities.

Pay factors will not be calculated for items measured and paid for by the Lump Sum or precast items accepted in accordance with Section 554. Except for concrete barrier rail, pay factors will not be calculated for items measured and paid for by the each. Concrete barrier rail will be tested and accepted the same as cast in place items.

Deleted: each

Deleted: that has concrete as a component poured on the project

Formatted: Font: Bold

Formatted: Font: Bold

Deleted: precast

NO COMMENTS

**FINAL
EFFECTIVE July 14, 2016**

551.03.8 Testing and Acceptance of Concrete

D. Acceptance of Concrete.

2. Classes General, Deck, Pave, Structure, Overlay and Drilled Shaft Concrete.

The overall lot pay factor (OLPF) will be calculated for bid items as shown in Table 551-10 and will be applied as a line item adjustment on the estimate.

TABLE 551-10

Class	Items
Deck	Include all items except metal bridge rail and bridge deck repair
Drilled Shaft	Include all items
Overlay-SF	Include all items
Pave	Include all items

Structure	Include concrete class bid items and Revise Barrier items
General	Include concrete class bid items Include items in Subsection 608 Include items in Subsection 609 Include items measured by the volume Exclude all other items

Note 1: The OLPF may be evaluated on other contract items that have significant equivalent concrete quantities.

Pay factors will not be calculated for items measured and paid for by the Lump Sum or precast items accepted in accordance with Section 554. Except for concrete barrier rail, pay factors will not be calculated for items measured and paid for by the each. Concrete barrier rail will be tested and accepted the same as cast-in-place items.